DAYLIGHT AND SUNLIGHT AMENITY

The Grange, Priory Lane, Roehampton, London SW15 5JQ

Change of Use from Offices to Residential (Class MA)

Report on Daylight and Sunlight Amenity Received within the Proposed Development

Client / Applicant	Knight Frank
Our ref	PS/KF/Roehampton
Prepared by	Paul Smith BSc (Hons) MRICS, Consil Limited
Date	22 September 2026

Contents

1 Introduction

2 Planning Policy and Guidance

3 Assessment Methodology

4 Assessment of Light Levels within the Development

5 Conclusion

Appendix A: Illuminance and Sunlight Exposure Drawings

Appendix B: Illuminance and Sunlight Exposure Results Spreadsheets

1 Introduction

- In accordance with your instructions, we have analysed the daylight and sunlight amenity that would be received within the proposed residential accommodation at The Grange, Roehampton ('the development').
- The site comprises a five-storey office building located within the Bank of England Sports Grounds. Me Architects propose to convert the building from office (Class E) use to residential (Class C3) use, to provide 48 self-contained flats, under Class MA of Part 3, Schedule 2 to the Town and Country Planning (General Permitted Development) (England) Order 2015 ('the GPDO'), as amended. No external alterations to the building are proposed.
- Class MA prior approval requires the local planning authority to consider, among other matters, the provision of adequate natural light in all habitable rooms of the dwellinghouses (paragraph MA.2(2)(f) of Schedule 2, Part 3 to the GPDO). For these purposes, a habitable room is one used for living or sleeping (including a combined living/kitchen/dining room), and does not include a kitchen that is not part of such a combined room, a bathroom, a corridor or other ancillary space.
- Because Class MA permitted development rights do not extend to an increase in the building's height, footprint or overall massing, and no external alterations are proposed, the proposal would not alter the daylight or sunlight amenity received by neighbouring properties. This report is accordingly confined to the daylight and sunlight amenity that would be received within the proposed dwellings, which is the material consideration for a Class MA prior approval application.
- Our assessment has been carried out using the daylight and sunlight targets set out in BS EN 17037 (2018) 'Daylight in Buildings', applying the climate-based daylight and sunlight modelling methodology described in Appendix F of the Building Research Establishment (BRE) Report 209, 'Site Layout Planning for Daylight and Sunlight: A Guide to Good Practice' (2022) ('the BRE guide').
- A total of 126 habitable rooms, across 48 flats on the ground to fourth floors, have been assessed, comprising bedrooms, living/kitchen/dining rooms ('LKDs'), studios, kitchens and combined living/dining rooms. The rooms tested are shown on the illuminance and sunlight exposure drawings in Appendix A.

2 Planning Policy and Guidance

Permitted Development – Class MA

Class MA of Part 3, Schedule 2 to the GPDO permits the change of use of a building from offices (Class E) to residential (Class C3), subject to prior approval by the local planning authority of certain specified matters. Paragraph MA.2(2)(f) requires the local planning authority to consider 'the provision of adequate natural light in all habitable rooms of the dwellinghouses'. This is a statutory prior approval test specific to Class MA schemes, and is the primary basis on which the daylight and sunlight amenity of this development falls to be judged.

National Policy

The National Planning Policy Framework: Plan-Making and National Decision-Making Policies (August 2026) ('the NPPF') addresses the daylight and sunlight amenity of new development at Policy P3 'Living Conditions and Pollution', in Chapter 17 'Pollution, Public Protection and Security', which states:

"Development proposals should… [p]rovide healthy living conditions for occupiers and users in terms of adequate access to light and avoiding exposure to levels of air, noise, artificial light or other sources of pollution which could have an unacceptable adverse effect on health and the quality of life. Where necessary suitable mitigation measures should be incorporated to secure acceptable living conditions." (Policy P3(2)(a))

Policy P3(2)(b) separately addresses impacts on neighbouring residents' daylight and sunlight, which is not engaged by this scheme as no external works are proposed.

Regional Policy – Greater London Authority

Paragraph D of Policy D6 'Housing Quality and Standards' of the London Plan (2021) states the following in respect of daylight and sunlight amenity:

"The design of development should provide sufficient daylight and sunlight to new and surrounding housing that is appropriate for its context, whilst avoiding overheating, minimising overshadowing and maximising the usability of outside amenity space."

The Mayor's 2023 Housing Design Standards LPG confirms that BRE guidance should be applied alongside consideration of the local context, and that daylight, passive solar gain and overheating should be balanced together in the design.

Local Policy – London Borough of Wandsworth

Policy DMS1 (General development principles: sustainable urban design and the quality of the environment) of the Wandsworth Local Plan (Development Management Policies Document) requires development not to cause unsatisfactory outlook, privacy or daylight/sunlight to existing or future occupiers, among other design quality criteria.

National Guidance – the BRE Guide and BS EN 17037

The BRE guide was updated in June 2022 and provides nationally recognised assessment methodologies for daylight and sunlight amenity. For the assessment of daylight and sunlight within new residential accommodation, the BRE guide adopts the climate-based daylight and sunlight modelling targets set out in BS EN 17037, which are the tests applied in this report.

"The advice given here is not mandatory and this document should not be seen as an instrument of planning policy; its aim is to help rather than constrain the designer. Although it gives numerical guidelines, these should be interpreted flexibly because natural lighting is only one of many factors in site layout design." (para. 1.6)

3 Assessment Methodology

Sources of Information

Our assessment has been prepared using the following information:

- Me Architects: proposed scheme drawings, received 4 September 2026;
- Zmapping Limited: 3D photogrammetry model of the existing building, received 3 September 2026;
- Consil site photography, taken 12 August 2026.

The photogrammetry survey is considered sufficiently accurate for the purposes of this daylight and sunlight amenity assessment.

Daylight within the Development – Illuminance (Spatial Daylight Autonomy)

Daylight within the proposed dwellings has been assessed using climate-based daylight modelling, based on weather data for the London area. This calculates the median illuminance (lux) received at assessment points across each room over a typical year. In accordance with BS EN 17037 and the BRE guide, a room is considered to achieve adequate daylight where the recommended illuminance is met across at least 50% of the room's

effective area for at least 50% of daylight hours. The recommended (target) illuminance is 100 lux in bedrooms, 150 lux in living rooms, LKDs and studios, and 200 lux in kitchens.

Sunlight within the Development – Sunlight Exposure

Sunlight within the proposed dwellings has been assessed using the Sunlight Exposure ('SE') test, which calculates the number of hours of direct sunlight received at a window on 21 March. The BRE guide and BS EN 17037 recommend that at least one habitable room in a dwelling, ideally a main living room, receives at least 1.5 hours of direct sunlight on that date. Results are rated High, Medium, Minimum or Failed, in accordance with BS EN 17037's own rating bands. Because the recommendation is expressed at the level of the dwelling, and not every individual room, we have assessed compliance on a per-flat basis, using the unit schedule provided, as well as on a per-room basis for completeness. A flat is considered to achieve the sunlight exposure recommendation where at least one of its habitable rooms is rated High, Medium or Minimum.

Scope of this Report

This report addresses only the daylight and sunlight amenity received within the proposed development. As no external alterations are proposed and the proposal does not increase the building's height, footprint or massing, there is no assessment of Vertical Sky Component, No Sky Line or Annual Probable Sunlight Hours to neighbouring properties, as would be required for a scheme involving new build or extension.

4 Assessment of Light Levels within the Development

We have analysed the daylight and sunlight availability to the 126 proposed habitable rooms within the development. The illuminance and sunlight exposure results, together with the location of the tested rooms and window references, are shown on the drawings in Appendix A. The full results spreadsheets are included in Appendix B.

We have reviewed the proposed layouts against the BS EN 17037 targets. As with any conversion of an existing building under Class MA, the scope to introduce new or enlarged window openings is limited, and the fenestration pattern of the retained office envelope is a fixed constraint on the design. As set out below, the results demonstrate that, notwithstanding this constraint, the majority of rooms would receive good levels of daylight, and where the guidance is not met this is generally because the room extends beyond the reach of a single existing window, with the living or sleeping area closest to the window well lit and the remainder of the room – typically a kitchen, secondary sleeping area, or the rear of a studio – designed to be predominantly artificially lit.

4.1 Overview

Floor	Rooms tested	Daylight (SDA) – meets guidance	Sunlight (SE) – High/Medium/Minimum
Ground	22	20 (91%)	8 (36%)
First	22	18 (82%)	7 (32%)
Second	28	28 (100%)	17 (61%)
Third	28	28 (100%)	17 (61%)
Fourth	26	24 (92%)	14 (54%)
Total	126	118 (94%)	63 (50%)

Table 1: Summary of daylight (SDA) and sunlight (SE) compliance by floor (room basis). The sunlight exposure recommendation is assessed at dwelling level in Section 4.3 – see Table 4.

4.2 Daylight

Overall, 118 of the 126 rooms assessed (94%) would meet the BS EN 17037 daylight guidance. The results by room type are set out in Table 2 below.

Room type	Rooms tested	Meeting guidance	%
LKD	41	36	88%
Bedroom	76	73	96%
Studio	5	5	100%
Kitchen	2	2	100%
Living/Dining	2	2	100%
Total	126	118	94%

Table 2: Daylight (SDA) compliance by room type.

The 8 rooms that do not meet the guidance are five large open-plan LKDs and three bedrooms, set out in Table 3. In every case, the room extends well beyond the depth that a single window wall can adequately daylight.

Floor	Room	Use	% of area meeting target lux
Ground	R13	LKD	39%

Floor	Room	Use	% of area meeting target lux
Ground	R15	Bedroom	48%
First	R8	LKD	41%
First	R9	Bedroom	29%
First	R14	Bedroom	30%
First	R15	LKD	38%
Fourth	R8	LKD	22%
Fourth	R13	LKD	15%

Table 3: Rooms not meeting the BS EN 17037 daylight (SDA) guidance.

Distribution of daylight within non-compliant rooms

The illuminance drawings in Appendix A illustrate why these rooms fall short of the 50% area threshold, and demonstrate that it is only the more remote part of each room that is affected. Image 1 below shows Rooms R8 and R9 at ground floor, two studio flats served by a single window wall. The area closest to the window (shaded yellow, over 300 lux) comfortably exceeds the target illuminance for a living space; it is only the rear third to half of each room, away from the window, that falls into the amber/purple range below the 150 lux target for a studio.




Image 1: Illuminance results for Rooms R8 and R9 (Studios), Ground floor. The window wall is at the bottom of each room.

Image 2 below shows Room R13, a ground floor LKD, where the pattern is repeated: high illuminance immediately in front of the window, falling away towards the rear of the room, where the kitchen area would be located.




Image 2: Illuminance result for Room R13 (LKD), Ground floor. The window wall is at the bottom of the room.

The same pattern is repeated consistently across the remaining non-compliant rooms, illustrated in Images 3 to 6 below.




Image 3: Illuminance result for Room R15 (Bedroom), Ground floor. The window wall is at the bottom of the room.




Image 4: Illuminance results for Rooms R8 (LKD) and R9 (Bedroom), First floor. The window wall is at the bottom of each room.




Image 5: Illuminance results for Rooms R14 (Bedroom) and R15 (LKD), First floor. The window wall is at the bottom of each room.




Image 6: Illuminance results for Rooms R8 and R13 (both LKDs), Fourth floor. The window is shown at the bottom of each room (W15 and W22 respectively).

In each of the 8 non-compliant rooms, the design places the living area, or the bed position in the case of the affected bedrooms, in the well-lit zone closest to the window, with the kitchen or a secondary part of the room positioned at the rear, away from the window, where it is intended to be predominantly artificially lit. This is a recognised and long-standing design response to deep-plan rooms served by a single window wall, and is the same approach adopted in previous schemes we have advised on. Under Class MA, the position and size of the existing window openings cannot readily be altered, so relocating or enlarging the fenestration to daylight the rear of these rooms is not a realistic option open to the design team; the only alternative would be to compartmentalise the rooms into smaller units, which would narrow the deep-plan floorplate into spaces with no outlook and would not, in our view, represent a better outcome for future occupiers.

4.3 Sunlight

Tested at the level of the dwelling, which is the correct basis under BS EN 17037, 32 of the 48 flats (67%) contain at least one room that achieves a High, Medium or Minimum sunlight exposure rating, and would therefore be considered to receive adequate sunlight amenity. The remaining 16 flats (33%) contain no room that receives any direct sunlight on 21 March.

Basis of assessment	Compliant	Total	%
Per dwelling (at least 1 room High/Medium/Minimum)	32	48	67%
Per room (High/Medium/Minimum)	63	126	50%

Table 4: Sunlight exposure (SE) compliance, tested per dwelling and per room.

On a room-by-room basis, 63 of the 126 rooms tested (50%) achieve a High, Medium or Minimum rating, set out by rating band in Table 5. The room-level figures are lower than the dwelling-level figure because several flats contain more than one habitable room, only one of which needs to meet the recommendation; a number of flats also contain a studio or a secondary kitchen tested separately, which, being served only by the same north-facing windows as the rest of the flat, does not add a further chance of compliance.

Rating	Rooms	%
High	32	25%
Medium	23	18%
Minimum	8	6%
Failed	63	50%

Table 5: Sunlight exposure (SE) ratings, all rooms tested.

The results correlate closely with window orientation. Of the windows serving rooms rated Failed, the great majority face within the northerly quadrant (orientations of 20° and 290°, both incapable of receiving direct sun), whereas the windows serving compliant rooms are predominantly oriented around 110° and 200° (broadly east-south-east and south-south-west). This is consistent with the orientation of the retained building envelope rather than any aspect of the internal layout, and is not a matter the design can readily address under Class MA, as it cannot alter the position of the building or its existing window openings.

Of the 16 flats that do not contain any compliant room, the great majority are served exclusively by windows on the site's north-facing elevations, ranging from single-aspect studios to larger two- and three-room flats where every room shares the same orientation. One flat is served in part by a more favourably-oriented window that nonetheless falls short of the sunlight exposure threshold, indicating that constrained window size and obstruction, as well as orientation, are contributing factors in that case. As noted in Section 1, standalone kitchens (i.e. those not combined with a living or dining area) do not, in any event, fall within the definition of a habitable room for the purposes of the Class MA natural light test, so the two secondary kitchens tested are not, strictly, determinative of compliance for the flats in which they sit.

4.4 Summary

In summary, the analysis demonstrates that adequate levels of daylight amenity would be received within the proposed development, with 94% of rooms meeting the BS EN 17037 guidance. Where daylight is restricted, this is concentrated in a small number of large, open-plan LKDs and bedrooms, and the results demonstrate that it is the area of each room closest to the window that receives good daylight, with only the rear of the room – typically the kitchen – falling below the target, consistent with a design intention for these areas to be predominantly artificially lit.

The sunlight results, tested correctly at dwelling level, show that two-thirds of the 48 flats (67%) would contain at least one room meeting the sunlight exposure recommendation. The remaining third are, in the great majority of cases, flats served exclusively by windows on the north-facing elevations of the retained envelope, an outcome that reflects the orientation of the existing building rather than any deficiency in the proposed internal layout, and is a direct consequence of the constraints inherent in adapting an existing office building under Class MA, where the position of the external walls and openings cannot be altered.

5 Conclusion

Our analysis has considered the daylight and sunlight amenity that would be received within the proposed residential accommodation at The Grange, Roehampton, following its change of use from offices to residential under Class MA of the GPDO.

The results show that 94% of the 126 rooms assessed would meet the BS EN 17037 guidance for daylight, and, tested correctly at dwelling level, 67% of the 48 flats would contain at least one room meeting the guidance for sunlight exposure. Where the guidance is not met, this is properly understood in the context of the constraints of converting an existing office building under permitted development rights, where the size, position and orientation of the existing window openings cannot be altered, and no external works are proposed to this scheme.


For daylight, the non-compliant rooms are all large, deep-plan LKDs and bedrooms in which the living or sleeping area nearest the window would receive good levels of daylight, with only the rear of the room – designed to be predominantly artificially lit – falling below the target. This is a considered design response to a deep floorplate served by a single, fixed window wall, and is preferable to compartmentalising these rooms into smaller spaces with no outlook.

For sunlight, the results correlate closely with the orientation of the retained building envelope, with the 16 non-compliant flats served, in the great majority of cases, only by north-facing windows that could not, under Class MA, be relocated or enlarged to introduce a more favourable aspect.

Taking these matters together, and having regard to the advisory and non-mandatory status of the BRE guide's numerical targets, the requirement under Policy P3(2)(a) of the NPPF (August 2026) and Policy DMS1 of the Wandsworth Local Plan for occupiers to have adequate access to light rather than to meet a specific numerical standard, and to the specific prior approval test at paragraph MA.2(2)(f) of the GPDO, it is our opinion that the proposed development would provide adequate natural light to future occupiers of the scheme.

Appendix A

ILLUMINANCE AND SUNLIGHT EXPOSURE DRAWINGS



Ground Floor

KEY

R1 Room Reference

Illuminance (Lux)

300 275 250 225 200 175 150 125 100 75 50 25 0

x% SDA (% of room area)

MI Median Illuminance (Lux)

SOURCES OF INFORMATION:

Me Architects proposed scheme received on 04/09/2026

3D photogrammetry model received from Zmapping Limited on 03/09/2026

Consil site photography taken on 12/08/2026

ANALYSIS PARAMETERS:

Maintenance Factor -
Unobstructed windows: 0.92
Obstructed windows: 0.76
Window diffuse transmittance - 0.68
Frame to Glazing Ratio - Bespoke
Reflectivities (internal materials) -
Walls: 0.80 Floors: 0.40
Ceilings: 0.80 Window frames: 0.60
Reflectivities (external materials R,G,B) -
Red Brick: 0.20 Concrete: 0.30
Medium Brick: 0.40 Light wood: 0.40
Light render: 0.60 Matt Aluminium: 0.45
All other reflectances: 0.20

CLIENT
Knight Frank

PROJECT
The Grange, Priory Lane, London SW15 5JQ

DRAWING TITLE
Illuminance (SDA or Spatial Daylight Autonomy) analysis

SCALE 1:150 @A3
DATE 16/09/2026
DRAWN BY BG
CHECKED BY PS
DWG No. D+S/1/ 501
REV.

CONSIL

THIS DRAWING IS COPYRIGHT OF CONSIL. DO NOT SCALE THIS DRAWING. IT MAY NOT BE COPIED (IN WHOLE OR IN PART), RETAINED OR DISCLOSED WITHOUT THE PRIOR WRITTEN CONSENT OF CONSIL. ALL INFORMATION DISPLAYED HAS BEEN PREPARED USING PHOTOGRAMMETRY THE BASIS FOR THE MODEL AND IS SUBJECT TO A COMPLETE VERIFIABLE SITE SURVEY BEING UNDERTAKEN AND OUR MODEL AND ANALYSIS BEING UPDATED ACCORDINGLY.



First Floor

KEY

R1 Room Reference

Illuminance (Lux)

300 275 250 225 200
175 150 125 100 75
50 25 0

x% SDA (% of room area)

MI Median Illuminance (Lux)

SOURCES OF INFORMATION:

Me Architects proposed scheme received on 04/09/2026

3D photogrammetry model received from Zmapping Limited on 03/09/2026

Consil site photography taken on 12/08/2026

ANALYSIS PARAMETERS:

Maintenance Factor -
Unobstructed windows: 0.92
Obstructed windows: 0.76
Window diffuse transmittance - 0.68
Frame to Glazing Ratio - Bespoke
Reflectivities (internal materials) -
Walls: 0.80 Floors: 0.40
Ceilings: 0.80 Window frames: 0.60
Reflectivities (external materials R,G,B) -
Red Brick: 0.20 Concrete: 0.30
Medium Brick: 0.40 Light wood: 0.40
Light render: 0.60 Matt Aluminium: 0.45
All other reflectances: 0.20

CLIENT
Knight Frank

PROJECT
The Grange, Priory Lane, London SW15 5JQ


DRAWING TITLE
Illuminance (SDA or Spatial Daylight Autonomy) analysis

SCALE 1:150 @A3
DATE 16/09/2026
DRAWN BY BG
CHECKED BY PS

DWG No. D+S /1/ 502
REV.

CONSIL

THIS DRAWING IS COPYRIGHT OF CONSIL. DO NOT SCALE THIS DRAWING. IT MAY NOT BE COPIED (IN WHOLE OR IN PART), RETAINED OR DISCLOSED WITHOUT THE PRIOR WRITTEN CONSENT OF CONSIL. ALL INFORMATION DISPLAYED HAS BEEN PREPARED USING PHOTOGRAMMETRY THE BASIS FOR THE MODEL AND IS SUBJECT TO A COMPLETE VERIFIABLE SITE SURVEY BEING UNDERTAKEN AND OUR MODEL AND ANALYSIS BEING UPDATED ACCORDINGLY.



Second Floor

KEY

R1 Room Reference

Illuminance (Lux)

300 275 250 225 200
175 150 125 100 75
50 25 0

x% SDA (% of room area)

MI Median Illuminance (Lux)

SOURCES OF INFORMATION:

Me Architects proposed scheme received on 04/09/2026

3D photogrammetry model received from Zmapping Limited on 03/09/2026

Consil site photography taken on 12/08/2026

ANALYSIS PARAMETERS:

Maintenance Factor -
Unobstructed windows: 0.92
Obstructed windows: 0.76
Window diffuse transmittance - 0.68
Frame to Glazing Ratio - Bespoke
Reflectivities (internal materials) -
Walls: 0.80 Floors: 0.40
Ceilings: 0.80 Window frames: 0.60
Reflectivities (external materials R,G,B) -
Red Brick: 0.20 Concrete: 0.30
Medium Brick: 0.40 Light wood: 0.40
Light render: 0.60 Matt Aluminium: 0.45
All other reflectances: 0.20

CLIENT
Knight Frank

PROJECT
The Grange, Priory Lane, London SW15 5JQ

DRAWING TITLE
Illuminance (SDA or Spatial Daylight Autonomy) analysis

SCALE 1:150 @A3
DATE 16/09/2026
DRAWN BY BG
CHECKED BY PS

DWG No. D+S /1/ 503
REV.

CONSIL

THIS DRAWING IS COPYRIGHT OF CONSIL. DO NOT SCALE THIS DRAWING. IT MAY NOT BE COPIED (IN WHOLE OR IN PART), RETAINED OR DISCLOSED WITHOUT THE PRIOR WRITTEN CONSENT OF CONSIL. ALL INFORMATION DISPLAYED HAS BEEN PREPARED USING PHOTOGRAMMETRY THE BASIS FOR THE MODEL AND IS SUBJECT TO A COMPLETE VERIFIABLE SITE SURVEY BEING UNDERTAKEN AND OUR MODEL AND ANALYSIS BEING UPDATED ACCORDINGLY.



Third Floor

KEY

R1 Room Reference

Illuminance (Lux)

300 275 250 225 200 175 150 125 100 75 50 25 0

x% SDA (% of room area)

MI Median Illuminance (Lux)

SOURCES OF INFORMATION:

Me Architects proposed scheme received on 04/09/2026

3D photogrammetry model received from Zmapping Limited on 03/09/2026

Consil site photography taken on 12/08/2026

ANALYSIS PARAMETERS:

Maintenance Factor -
Unobstructed windows: 0.92
Obstructed windows: 0.76
Window diffuse transmittance - 0.68
Frame to Glazing Ratio - Bespoke
Reflectivities (internal materials) -
Walls: 0.80 Floors: 0.40
Ceilings: 0.80 Window frames: 0.60
Reflectivities (external materials R,G,B) -
Red Brick: 0.20 Concrete: 0.30
Medium Brick: 0.40 Light wood: 0.40
Light render: 0.60 Matt Aluminium: 0.45
All other reflectances: 0.20

CLIENT
Knight Frank

PROJECT
The Grange, Priory Lane, London SW15 5JQ

DRAWING TITLE
Illuminance (SDA or Spatial Daylight Autonomy) analysis

SCALE 1:150 @A3
DATE 16/09/2026
DRAWN BY BG
CHECKED BY PS

DWG No. D+S /1/ 504
REV.

CONSIL

THIS DRAWING IS COPYRIGHT OF CONSIL. DO NOT SCALE THIS DRAWING. IT MAY NOT BE COPIED (IN WHOLE OR IN PART), RETAINED OR DISCLOSED WITHOUT THE PRIOR WRITTEN CONSENT OF CONSIL. ALL INFORMATION DISPLAYED HAS BEEN PREPARED USING PHOTOGRAMMETRY THE BASIS FOR THE MODEL AND IS SUBJECT TO A COMPLETE VERIFIABLE SITE SURVEY BEING UNDERTAKEN AND OUR MODEL AND ANALYSIS BEING UPDATED ACCORDINGLY.



Fourth Floor

KEY

R1 Room Reference

Illuminance (Lux)

300	175	50
275	150	25
250	125	0
225	100	
200	75	

x% SDA (% of room area)

MI Median Illuminance (Lux)

SOURCES OF INFORMATION:

Me Architects proposed scheme received on 04/09/2026

3D photogrammetry model received from Zmapping Limited on 03/09/2026

Consil site photography taken on 12/08/2026

ANALYSIS PARAMETERS:

Maintenance Factor -
Unobstructed windows: 0.92
Obstructed windows: 0.76
Window diffuse transmittance - 0.68
Frame to Glazing Ratio - Bespoke
Reflectivities (internal materials) -
Walls: 0.80 Floors: 0.40
Ceilings: 0.80 Window frames: 0.60
Reflectivities (external materials R,G,B) -
Red Brick: 0.20 Concrete: 0.30
Medium Brick: 0.40 Light wood: 0.40
Light render: 0.60 Matt Aluminium: 0.45
All other reflectances: 0.20

CLIENT
Knight Frank

PROJECT
The Grange, Priory Lane,
London SW15 5JQ

DRAWING TITLE
Illuminance (SDA or Spatial Daylight Autonomy) analysis

SCALE	DATE
1:150 @A3	16/09/2026
DRAWN BY	CHECKED BY
BG	PS

DWG No.	REV.
D+S /1/ 505	

CONSIL

THIS DRAWING IS COPYRIGHT OF CONSIL. DO NOT SCALE THIS DRAWING. IT MAY NOT BE COPIED (IN WHOLE OR IN PART), RETAINED OR DISCLOSED WITHOUT THE PRIOR WRITTEN CONSENT OF CONSIL. ALL INFORMATION DISPLAYED HAS BEEN PREPARED USING PHOTOGRAMMETRY THE BASIS FOR THE MODEL AND IS SUBJECT TO A COMPLETE VERIFIABLE SITE SURVEY BEING UNDERTAKEN AND OUR MODEL AND ANALYSIS BEING UPDATED ACCORDINGLY.

Appendix B

ILLUMINANCE AND SUNLIGHT EXPOSURE RESULTS SPREADSHEETS

Project Name: 2026 09 10
Project No.:
Report Title: SDA BS En17037 Analysis - Proposed Scheme
Date of Analysis: 11/09/2026

										Criteria				
Floor Ref	Room Ref	Room Attribute	Property Type	Room Use	Room Area m2	Effective Area	Median Lux	Area Meeting Req Lux	% of Area Meeting Req Lux	Req Lux	Req % of Effective Area	Req % of Daylight Hours	Daylight Hours	Meets Criteria
						Proposed								
Ground	R1	Unit 5	Residential	LKD	32.32	25.47	341	25.47	100%	150	50%	50%	4380	YES
	R2	Unit 5	Residential	Bedroom	12.80	8.70	214	8.70	100%	100	50%	50%	4380	YES
	R3	Unit 5	Residential	Bedroom	12.86	8.76	210	8.76	100%	100	50%	50%	4380	YES
	R4	Unit 5	Residential	Bedroom	12.79	8.68	435	8.68	100%	100	50%	50%	4380	YES
	R5	Unit 4	Residential	Bedroom	9.79	6.37	303	6.37	100%	100	50%	50%	4380	YES
	R6	Unit 4	Residential	LKD	22.56	16.68	678	16.68	100%	150	50%	50%	4380	YES
	R7	Unit 4	Residential	Bedroom	12.03	8.17	490	8.17	100%	100	50%	50%	4380	YES
	R8	Unit 3	Residential	Studio	29.15	22.52	159	12.40	55%	150	50%	50%	4380	YES
	R9	Unit 2	Residential	Studio	27.37	20.49	166	13.75	67%	150	50%	50%	4380	YES
	R10	Unit 1	Residential	Studio	29.07	21.99	211	17.00	77%	150	50%	50%	4380	YES
	R11	Unit 9	Residential	Bedroom	10.50	6.96	262	6.96	100%	100	50%	50%	4380	YES
	R12	Unit 9	Residential	Bedroom	11.83	7.96	257	7.96	100%	100	50%	50%	4380	YES
	R13	Unit 9	Residential	LKD	24.06	16.15	129	6.31	39%	150	50%	50%	4380	NO
	R14	Unit 8	Residential	LKD	21.50	16.17	201	14.27	88%	150	50%	50%	4380	YES
	R15	Unit 8	Residential	Bedroom	14.07	9.71	97	4.62	48%	100	50%	50%	4380	NO
	R16	Unit 7	Residential	Bedroom	11.87	8.13	458	8.13	100%	100	50%	50%	4380	YES
	R17	Unit 7	Residential	LKD	22.56	16.76	734	16.76	100%	150	50%	50%	4380	YES
	R18	Unit 7	Residential	Bedroom	10.48	6.94	365	6.94	100%	100	50%	50%	4380	YES
	R19	Unit 6	Residential	Bedroom	12.80	8.73	561	8.73	100%	100	50%	50%	4380	YES
	R20	Unit 6	Residential	Bedroom	12.86	8.78	245	8.78	100%	100	50%	50%	4380	YES
	R21	Unit 6	Residential	Bedroom	12.80	8.73	240	8.73	100%	100	50%	50%	4380	YES
	R22	Unit 6	Residential	LKD	33.13	26.27	421	26.27	100%	150	50%	50%	4380	YES
First	R1	Unit 15	Residential	LKD	23.11	17.68	319	17.59	100%	150	50%	50%	4380	YES
	R2	Unit 15	Residential	Bedroom	13.77	9.62	519	9.62	100%	100	50%	50%	4380	YES
	R3	Unit 14	Residential	Bedroom	11.39	7.68	325	7.68	100%	100	50%	50%	4380	YES
	R4	Unit 14	Residential	LKD	24.35	17.20	337	13.17	77%	150	50%	50%	4380	YES
	R5	Unit 13	Residential	Bedroom	9.80	6.39	350	6.39	100%	100	50%	50%	4380	YES
	R6	Unit 13	Residential	LKD	22.57	16.69	731	16.69	100%	150	50%	50%	4380	YES
	R7	Unit 13	Residential	Bedroom	12.24	8.35	524	8.35	100%	100	50%	50%	4380	YES
	R8	Unit 12	Residential	LKD	40.14	32.03	125	13.15	41%	150	50%	50%	4380	NO
	R9	Unit 12	Residential	Bedroom	20.68	14.98	75	4.35	29%	100	50%	50%	4380	NO
	R10	Unit 11	Residential	LKD	31.53	24.83	218	18.79	76%	150	50%	50%	4380	YES
	R11	Unit 11	Residential	Bedroom	11.56	7.80	269	7.80	100%	100	50%	50%	4380	YES
	R12	Unit 10	Residential	Bedroom	12.01	8.20	286	8.20	100%	100	50%	50%	4380	YES
	R13	Unit 10	Residential	LKD	31.75	25.00	230	20.23	81%	150	50%	50%	4380	YES
	R14	Unit 19	Residential	Bedroom	20.71	15.01	73	4.45	30%	100	50%	50%	4380	NO
	R15	Unit 19	Residential	LKD	40.84	32.69	117	12.36	38%	150	50%	50%	4380	NO
	R16	Unit 18	Residential	Bedroom	11.61	7.91	503	7.91	100%	100	50%	50%	4380	YES
	R17	Unit 18	Residential	LKD	22.51	16.78	837	16.78	100%	150	50%	50%	4380	YES

	R18	Unit 18	Residential	Bedroom	10.41	6.86	439	6.86	100%	100	50%	50%	4380	YES
	R19	Unit 17	Residential	LKD	24.92	17.58	403	13.87	79%	150	50%	50%	4380	YES
	R20	Unit 17	Residential	Bedroom	11.84	8.06	384	8.06	100%	100	50%	50%	4380	YES
	R21	Unit 16	Residential	Bedroom	13.99	9.80	675	9.80	100%	100	50%	50%	4380	YES
	R22	Unit 16	Residential	LKD	23.65	18.19	395	18.19	100%	150	50%	50%	4380	YES
Second	R1	Unit 25	Residential	Bedroom	16.85	11.83	313	11.83	100%	100	50%	50%	4380	YES
	R2	Unit 25	Residential	Bedroom	10.66	7.07	326	7.07	100%	100	50%	50%	4380	YES
	R3	Unit 25	Residential	LKD	20.70	14.25	326	11.01	77%	150	50%	50%	4380	YES
	R4	Unit 24	Residential	Studio	26.04	20.14	292	20.14	100%	150	50%	50%	4380	YES
	R5	Unit 23	Residential	Bedroom	9.60	6.16	340	6.16	100%	100	50%	50%	4380	YES
	R6	Unit 23	Residential	LKD	20.65	15.02	741	15.02	100%	150	50%	50%	4380	YES
	R7	Unit 23	Residential	Bedroom	11.60	7.79	578	7.79	100%	100	50%	50%	4380	YES
	R8	Unit 22	Residential	LKD	19.67	13.35	308	9.68	72%	150	50%	50%	4380	YES
	R9	Unit 22	Residential	Bedroom	12.64	8.52	176	8.52	100%	100	50%	50%	4380	YES
	R10	Unit 21	Residential	LKD	35.00	26.66	428	26.66	100%	150	50%	50%	4380	YES
	R11	Unit 20	Residential	LKD	35.48	27.13	443	27.13	100%	150	50%	50%	4380	YES
	R12	Unit 29	Residential	Bedroom	9.10	5.83	237	5.83	100%	100	50%	50%	4380	YES
	R13	Unit 29	Residential	LKD	20.62	14.19	294	10.37	73%	150	50%	50%	4380	YES
	R14	Unit 28	Residential	Bedroom	11.53	7.85	507	7.85	100%	100	50%	50%	4380	YES
	R15	Unit 28	Residential	LKD	22.34	16.63	825	16.63	100%	150	50%	50%	4380	YES
	R16	Unit 28	Residential	Bedroom	10.42	6.88	453	6.88	100%	100	50%	50%	4380	YES
	R17	Unit 27	Residential	LKD	24.49	17.32	415	13.62	79%	150	50%	50%	4380	YES
	R18	Unit 27	Residential	Bedroom	11.44	7.73	399	7.73	100%	100	50%	50%	4380	YES
	R19	Unit 26	Residential	Bedroom	14.01	9.82	692	9.82	100%	100	50%	50%	4380	YES
	R20	Unit 26	Residential	LKD	23.66	18.18	375	18.18	100%	150	50%	50%	4380	YES
	R21	Unit 29	Residential	Bedroom	14.30	10.12	291	10.12	100%	100	50%	50%	4380	YES
	R22	Unit 20	Residential	Bedroom	12.82	8.88	255	8.88	100%	100	50%	50%	4380	YES
	R23	Unit 20	Residential	Bedroom	11.52	7.80	338	7.80	100%	100	50%	50%	4380	YES
	R24	Unit 20	Residential	Bedroom	11.52	7.80	332	7.80	100%	100	50%	50%	4380	YES
	R25	Unit 21	Residential	Bedroom	11.59	7.85	327	7.85	100%	100	50%	50%	4380	YES
	R26	Unit 21	Residential	Bedroom	11.59	7.85	324	7.85	100%	100	50%	50%	4380	YES
	R27	Unit 21	Residential	Bedroom	12.72	8.80	236	8.80	100%	100	50%	50%	4380	YES
	R28	Unit 22	Residential	Bedroom	14.36	10.18	299	10.18	100%	100	50%	50%	4380	YES
Third	R1	Unit 35	Residential	Bedroom	16.85	11.83	302	11.83	100%	100	50%	50%	4380	YES
	R2	Unit 35	Residential	Bedroom	10.66	7.08	305	7.08	100%	100	50%	50%	4380	YES
	R3	Unit 35	Residential	LKD	20.70	14.25	311	11.29	79%	150	50%	50%	4380	YES
	R4	Unit 34	Residential	Studio	26.04	20.14	280	20.14	100%	150	50%	50%	4380	YES
	R5	Unit 33	Residential	Bedroom	9.60	6.16	316	6.16	100%	100	50%	50%	4380	YES
	R6	Unit 33	Residential	LKD	20.65	14.97	698	14.97	100%	150	50%	50%	4380	YES
	R7	Unit 33	Residential	Bedroom	11.60	7.76	550	7.76	100%	100	50%	50%	4380	YES
	R8	Unit 32	Residential	LKD	20.17	13.78	284	9.71	70%	150	50%	50%	4380	YES
	R9	Unit 32	Residential	Bedroom	11.90	7.71	174	7.71	100%	100	50%	50%	4380	YES
	R10	Unit 31	Residential	LKD	34.12	25.93	405	25.93	100%	150	50%	50%	4380	YES
	R11	Unit 30	Residential	LKD	35.15	26.86	418	26.86	100%	150	50%	50%	4380	YES
	R12	Unit 39	Residential	Bedroom	8.56	5.40	220	5.40	100%	100	50%	50%	4380	YES
	R13	Unit 39	Residential	LKD	20.90	14.41	264	10.64	74%	150	50%	50%	4380	YES
	R14	Unit 38	Residential	Bedroom	11.53	7.82	473	7.82	100%	100	50%	50%	4380	YES
	R15	Unit 38	Residential	LKD	22.37	16.65	781	16.65	100%	150	50%	50%	4380	YES
	R16	Unit 38	Residential	Bedroom	10.41	6.87	425	6.87	100%	100	50%	50%	4380	YES
	R17	Unit 37	Residential	LKD	24.39	17.14	409	13.45	78%	150	50%	50%	4380	YES

	R18	Unit 37	Residential	Bedroom	11.43	7.72	387	7.72	100%	100	50%	50%	4380	YES
	R19	Unit 36	Residential	Bedroom	14.01	9.82	664	9.82	100%	100	50%	50%	4380	YES
	R20	Unit 36	Residential	LKD	23.65	18.19	378	18.19	100%	150	50%	50%	4380	YES
	R21	Unit 39	Residential	Bedroom	14.63	10.40	299	10.40	100%	100	50%	50%	4380	YES
	R22	Unit 30	Residential	Bedroom	12.83	8.89	246	8.89	100%	100	50%	50%	4380	YES
	R23	Unit 30	Residential	Bedroom	11.52	7.80	323	7.80	100%	100	50%	50%	4380	YES
	R24	Unit 30	Residential	Bedroom	11.52	7.80	323	7.80	100%	100	50%	50%	4380	YES
	R25	Unit 31	Residential	Bedroom	11.54	7.81	328	7.81	100%	100	50%	50%	4380	YES
	R26	Unit 31	Residential	Bedroom	11.54	7.81	328	7.81	100%	100	50%	50%	4380	YES
	R27	Unit 31	Residential	Bedroom	12.58	8.68	250	8.68	100%	100	50%	50%	4380	YES
	R28	Unit 32	Residential	Bedroom	14.46	10.26	334	10.26	100%	100	50%	50%	4380	YES
Fourth	R1	Unit 44	Residential	LKD	32.79	25.89	226	24.83	96%	150	50%	50%	4380	YES
	R2	Unit 44	Residential	Bedroom	12.51	8.47	211	8.47	100%	100	50%	50%	4380	YES
	R3	Unit 44	Residential	Bedroom	12.37	8.36	203	8.36	100%	100	50%	50%	4380	YES
	R4	Unit 44	Residential	Bedroom	12.54	8.46	394	8.46	100%	100	50%	50%	4380	YES
	R5	Unit 43	Residential	Bedroom	10.01	6.52	260	6.52	100%	100	50%	50%	4380	YES
	R6	Unit 43	Residential	LKD	21.87	16.07	539	16.07	100%	150	50%	50%	4380	YES
	R7	Unit 43	Residential	Bedroom	11.83	7.97	474	7.97	100%	100	50%	50%	4380	YES
	R8	Unit 42	Residential	LKD	29.61	22.62	83	5.06	22%	150	50%	50%	4380	NO
	R9	Unit 41	Residential	LD	16.93	12.12	401	12.12	100%	150	50%	50%	4380	YES
	R10	Unit 41	Residential	Kitchen	8.47	5.04	247	4.36	86%	200	50%	50%	4380	YES
	R11	Unit 40	Residential	Kitchen	8.35	4.97	272	4.88	98%	200	50%	50%	4380	YES
	R12	Unit 40	Residential	LD	16.93	12.12	365	12.12	100%	150	50%	50%	4380	YES
	R13	Unit 48	Residential	LKD	31.35	24.24	69	3.60	15%	150	50%	50%	4380	NO
	R14	Unit 47	Residential	Bedroom	11.55	7.85	398	7.85	100%	100	50%	50%	4380	YES
	R15	Unit 47	Residential	LKD	22.37	16.65	628	16.65	100%	150	50%	50%	4380	YES
	R16	Unit 47	Residential	Bedroom	10.41	6.87	353	6.87	100%	100	50%	50%	4380	YES
	R17	Unit 46	Residential	LKD	24.25	17.02	328	12.72	75%	150	50%	50%	4380	YES
	R18	Unit 46	Residential	Bedroom	11.33	7.64	338	7.64	100%	100	50%	50%	4380	YES
	R19	Unit 45	Residential	Bedroom	13.86	9.69	571	9.69	100%	100	50%	50%	4380	YES
	R20	Unit 45	Residential	LKD	23.65	18.19	237	18.01	99%	150	50%	50%	4380	YES
	R21	Unit 48	Residential	Bedroom	15.18	10.84	152	6.95	64%	100	50%	50%	4380	YES
	R22	Unit 40	Residential	Bedroom	10.68	7.12	266	7.12	100%	100	50%	50%	4380	YES
	R23	Unit 40	Residential	Bedroom	12.21	8.34	286	8.34	100%	100	50%	50%	4380	YES
	R24	Unit 41	Residential	Bedroom	12.04	8.20	312	8.20	100%	100	50%	50%	4380	YES
	R25	Unit 41	Residential	Bedroom	10.58	7.04	287	7.04	100%	100	50%	50%	4380	YES
	R26	Unit 42	Residential	Bedroom	15.14	10.81	156	7.48	69%	100	50%	50%	4380	YES

Property	Number of Rooms Tested	Rooms satisfying Criteria		Rooms not satisfying Criteria
		No.	%	
Proposed	126	118	94%	8
Total	**126**	**118**	**94%**	**8**

Project Name: 2026 09 10
Project No.:
Report Title: Sunlight Exposure Analysis - Proposed Scheme
Date: 11/09/2026

Floor Ref	Room Ref	Room Attribute	Property Type	Room Use	Window Ref	Window Orientation	Sunlight Exposure	Rating
				Proposed				
Ground	R1	Unit 05	Residential	LKD	W1	110°	2.100	
					W2	20°N	0.000	
					W3	20°N	0.000	
					W4	20°N	0.000	
							2.100	Minimum
Ground	R2	Unit 05	Residential	Bedroom	W5	20°N	0.000	
							0.000	Failed
Ground	R3	Unit 05	Residential	Bedroom	W6	20°N	0.000	
							0.000	Failed
Ground	R4	Unit 05	Residential	Bedroom	W7	20°N	0.000	
					W8	20°N	0.000	
							0.000	Failed
Ground	R5	Unit 04	Residential	Bedroom	W9	20°N	0.000	
							0.000	Failed
Ground	R6	Unit 04	Residential	LKD	W10	20°N	0.000	
					W11	20°N	0.000	
					W12	290°N	1.400	
					W13	290°N	1.400	
							1.400	Failed
Ground	R7	Unit 04	Residential	Bedroom	W14	290°N	1.400	
					W15	200°	2.200	
							3.600	Medium
Ground	R8	Unit 03	Residential	Studio	W16	290°N	0.000	
					W17	290°N	0.400	
							0.400	Failed
Ground	R9	Unit 02	Residential	Studio	W18	290°N	0.000	
					W19	290°N	0.600	
							0.600	Failed
Ground	R10	Unit 01	Residential	Studio	W20	290°N	0.500	
					W21	290°N	0.000	
							0.500	Failed
Ground	R11	Unit 09	Residential	Bedroom	W22	290°N	0.600	
							0.600	Failed
Ground	R12	Unit 09	Residential	Bedroom	W23	290°N	0.600	
							0.600	Failed
Ground	R13	Unit 09	Residential	LKD	W24	290°N	0.600	
							0.600	Failed
Ground	R14	Unit 08	Residential	LKD	W25	290°N	0.000	
					W26	290°N	0.300	

							0.300	Failed
Ground	R15	Unit 08	Residential	Bedroom	W27	290°N	0.000	
							0.000	Failed
Ground	R16	Unit 07	Residential	Bedroom	W28	20°N	0.000	
					W29	290°N	1.200	
							1.200	Failed
Ground	R17	Unit 07	Residential	LKD	W30	290°N	1.200	
					W31	290°N	1.200	
					W32	200°	4.200	
					W33	200°	6.400	
							6.500	High
Ground	R18	Unit 07	Residential	Bedroom	W34	200°	6.400	
							6.400	High
Ground	R19	Unit 06	Residential	Bedroom	W35	200°	6.400	
					W36	200°	6.400	
							6.400	High
Ground	R20	Unit 06	Residential	Bedroom	W37	200°	6.400	
							6.400	High
Ground	R21	Unit 06	Residential	Bedroom	W38	200°	6.400	
							6.400	High
Ground	R22	Unit 06	Residential	LKD	W39	200°	6.400	
					W40	200°	6.400	
					W41	200°	4.200	
					W42	110°	4.000	
							9.400	High
First	R1	Unit 15	Residential	LKD	W1	110°	1.000	
					W2	20°N	0.000	
					W3	20°N	0.000	
							1.000	Failed
First	R2	Unit 15	Residential	Bedroom	W4	20°N	0.000	
					W5	20°N	0.000	
							0.000	Failed
First	R3	Unit 14	Residential	Bedroom	W6	20°N	0.000	
							0.000	Failed
First	R4	Unit 14	Residential	LKD	W7	20°N	0.000	
					W8	20°N	0.000	
							0.000	Failed
First	R5	Unit 13	Residential	Bedroom	W9	20°N	0.000	
							0.000	Failed
First	R6	Unit 13	Residential	LKD	W10	20°N	0.000	
					W11	20°N	0.000	
					W12	290°N	1.400	
					W13	290°N	1.400	
							1.400	Failed
First	R7	Unit 13	Residential	Bedroom	W14	290°N	1.400	
					W15	200°	2.300	
							3.700	Medium
First	R8	Unit 12	Residential	LKD	W16	290°N	0.000	
					W17	290°N	0.800	
							0.800	Failed
First	R9	Unit 12	Residential	Bedroom	W18	290°N	0.000	

							0.000	Failed
First	R10	Unit 11	Residential	LKD	W19	290°N	1.000	
					W20	290°N	1.000	
							1.000	Failed
First	R11	Unit 11	Residential	Bedroom	W21	290°N	0.000	
							0.000	Failed
First	R12	Unit 10	Residential	Bedroom	W22	290°N	1.400	
							1.400	Failed
First	R13	Unit 10	Residential	LKD	W23	290°N	1.400	
					W24	290°N	1.400	
							1.400	Failed
First	R14	Unit 19	Residential	Bedroom	W25	290°N	0.000	
							0.000	Failed
First	R15	Unit 19	Residential	LKD	W26	290°N	0.300	
					W27	290°N	0.000	
							0.300	Failed
First	R16	Unit 18	Residential	Bedroom	W28	20°N	0.000	
					W29	290°N	1.100	
							1.100	Failed
First	R17	Unit 18	Residential	LKD	W30	290°N	1.100	
					W31	290°N	1.100	
					W32	200°	4.200	
					W33	200°	6.400	
							6.500	High
First	R18	Unit 18	Residential	Bedroom	W34	200°	6.400	
							6.400	High
First	R19	Unit 17	Residential	LKD	W35	200°	6.400	
					W36	200°	6.400	
							6.400	High
First	R20	Unit 17	Residential	Bedroom	W37	200°	6.400	
							6.400	High
First	R21	Unit 16	Residential	Bedroom	W38	200°	6.400	
					W39	200°	6.400	
							6.400	High
First	R22	Unit 16	Residential	LKD	W40	200°	6.400	
					W41	200°	4.200	
					W42	110°	0.600	
							7.000	High
Second	R1	Unit 25	Residential	Bedroom	W1	20°N	0.000	
					W2	20°N	0.000	
							0.000	Failed
Second	R2	Unit 25	Residential	Bedroom	W3	20°N	0.000	
							0.000	Failed
Second	R3	Unit 25	Residential	LKD	W4	20°N	0.000	
					W5	20°N	0.000	
							0.000	Failed
Second	R4	Unit 24	Residential	Studio	W6	20°N	0.000	
					W7	20°N	0.000	
							0.000	Failed
Second	R5	Unit 23	Residential	Bedroom	W8	20°N	0.000	
							0.000	Failed

Second	R6	Unit 23	Residential	LKD	W9	20°N	0.000	
					W10	20°N	0.000	
					W11	290°N	1.400	
					W12	290°N	1.400	
							1.400	Failed
Second	R7	Unit 23	Residential	Bedroom	W13	290°N	1.400	
					W14	200°	2.500	
							4.000	Medium
Second	R8	Unit 22	Residential	LKD	W15	290°N	0.600	
					W16	290°N	1.400	
							1.400	Failed
Second	R9	Unit 22	Residential	Bedroom	W17	290°N	0.600	
							0.600	Failed
Second	R10	Unit 21	Residential	LKD	W18	290°N	1.600	
					W19	290°N	1.600	
					W20	290°N	0.100	
							1.600	Minimum
Second	R11	Unit 20	Residential	LKD	W21	290°N	1.800	
					W22	290°N	1.800	
					W23	290°N	1.600	
							1.800	Minimum
Second	R12	Unit 29	Residential	Bedroom	W24	290°N	1.000	
							1.000	Failed
Second	R13	Unit 29	Residential	LKD	W25	290°N	0.400	
					W26	290°N	0.000	
							0.400	Failed
Second	R14	Unit 28	Residential	Bedroom	W27	20°N	0.000	
					W28	290°N	1.100	
							1.100	Failed
Second	R15	Unit 28	Residential	LKD	W29	290°N	1.100	
					W30	290°N	1.100	
					W31	200°	4.200	
					W32	200°	6.400	
							6.500	High
Second	R16	Unit 28	Residential	Bedroom	W33	200°	6.400	
							6.400	High
Second	R17	Unit 27	Residential	LKD	W34	200°	6.400	
					W35	200°	6.400	
							6.400	High
Second	R18	Unit 27	Residential	Bedroom	W36	200°	6.400	
							6.400	High
Second	R19	Unit 26	Residential	Bedroom	W37	200°	6.400	
					W38	200°	6.400	
							6.400	High
Second	R20	Unit 26	Residential	LKD	W39	200°	6.400	
					W40	200°	4.200	
					W41	110°	0.600	
							7.000	High
Second	R21	Unit 29	Residential	Bedroom	W42	110°	1.500	
					W43	110°	2.300	
							2.300	Minimum

Second	R22	Unit 20	Residential	Bedroom	W44	110°	3.600	
							3.600	Medium
Second	R23	Unit 20	Residential	Bedroom	W45	110°	3.600	
							3.600	Medium
Second	R24	Unit 20	Residential	Bedroom	W46	110°	3.600	
							3.600	Medium
Second	R25	Unit 21	Residential	Bedroom	W47	110°	3.600	
							3.600	Medium
Second	R26	Unit 21	Residential	Bedroom	W48	110°	3.500	
							3.500	Medium
Second	R27	Unit 21	Residential	Bedroom	W49	110°	3.600	
							3.600	Medium
Second	R28	Unit 22	Residential	Bedroom	W50	110°	2.200	
					W51	110°	2.400	
							2.700	Minimum
Third	R1	Unit 35	Residential	Bedroom	W1	20°N	0.000	
					W2	20°N	0.000	
							0.000	Failed
Third	R2	Unit 35	Residential	Bedroom	W3	20°N	0.000	
							0.000	Failed
Third	R3	Unit 35	Residential	LKD	W4	20°N	0.000	
					W5	20°N	0.000	
							0.000	Failed
Third	R4	Unit 34	Residential	Studio	W6	20°N	0.000	
					W7	20°N	0.000	
							0.000	Failed
Third	R5	Unit 33	Residential	Bedroom	W8	20°N	0.000	
							0.000	Failed
Third	R6	Unit 33	Residential	LKD	W9	20°N	0.000	
					W10	20°N	0.000	
					W11	290°N	1.400	
					W12	290°N	1.400	
							1.400	Failed
Third	R7	Unit 33	Residential	Bedroom	W13	290°N	1.400	
					W14	200°	2.900	
							4.300	High
Third	R8	Unit 32	Residential	LKD	W15	290°N	0.600	
					W16	290°N	1.400	
							1.400	Failed
Third	R9	Unit 32	Residential	Bedroom	W17	290°N	0.600	
							0.600	Failed
Third	R10	Unit 31	Residential	LKD	W18	290°N	1.600	
					W19	290°N	1.600	
					W20	290°N	0.100	
							1.600	Minimum
Third	R11	Unit 30	Residential	LKD	W21	290°N	1.800	
					W22	290°N	1.800	
					W23	290°N	1.600	
							1.800	Minimum
Third	R12	Unit 39	Residential	Bedroom	W24	290°N	1.000	
							1.000	Failed

Third	R13	Unit 39	Residential	LKD	W25	290°N	0.400	
					W26	290°N	0.000	
							0.400	Failed
Third	R14	Unit 38	Residential	Bedroom	W27	20°N	0.000	
					W28	290°N	1.100	
							1.100	Failed
Third	R15	Unit 38	Residential	LKD	W29	290°N	1.100	
					W30	290°N	1.100	
					W31	200°	4.200	
					W32	200°	6.400	
							6.500	High
Third	R16	Unit 38	Residential	Bedroom	W33	200°	6.400	
							6.400	High
Third	R17	Unit 37	Residential	LKD	W34	200°	6.400	
					W35	200°	6.400	
							6.400	High
Third	R18	Unit 37	Residential	Bedroom	W36	200°	6.400	
							6.400	High
Third	R19	Unit 36	Residential	Bedroom	W37	200°	6.400	
					W38	200°	6.400	
							6.400	High
Third	R20	Unit 36	Residential	LKD	W39	200°	6.400	
					W40	200°	4.200	
					W41	110°	0.900	
							7.200	High
Third	R21	Unit 39	Residential	Bedroom	W42	110°	1.700	
					W43	110°	3.100	
							3.100	Medium
Third	R22	Unit 30	Residential	Bedroom	W44	110°	4.000	
							4.000	Medium
Third	R23	Unit 30	Residential	Bedroom	W45	110°	4.000	
							4.000	Medium
Third	R24	Unit 30	Residential	Bedroom	W46	110°	4.000	
							4.000	Medium
Third	R25	Unit 31	Residential	Bedroom	W47	110°	4.000	
							4.000	Medium
Third	R26	Unit 31	Residential	Bedroom	W48	110°	4.000	
							4.000	Medium
Third	R27	Unit 31	Residential	Bedroom	W49	110°	4.000	
							4.000	Medium
Third	R28	Unit 32	Residential	Bedroom	W50	110°	3.000	
					W51	110°	3.400	
							3.600	Medium
Fourth	R1	Unit 44	Residential	LKD	W1	20°N	0.000	
					W2	20°N	0.000	
					W3	20°N	0.000	
							0.000	Failed
Fourth	R2	Unit 44	Residential	Bedroom	W4	20°N	0.000	
							0.000	Failed
Fourth	R3	Unit 44	Residential	Bedroom	W5	20°N	0.000	
							0.000	Failed

Fourth	R4	Unit 44	Residential	Bedroom	W6	20°N	0.000	
					W7	20°N	0.000	
							0.000	Failed
Fourth	R5	Unit 43	Residential	Bedroom	W8	20°N	0.000	
							0.000	Failed
Fourth	R6	Unit 43	Residential	LKD	W9	20°N	0.000	
					W10	20°N	0.000	
					W11	290°N	1.400	
					W12	290°N	1.400	
							1.400	Failed
Fourth	R7	Unit 43	Residential	Bedroom	W13	290°N	1.400	
					W14	200°	4.200	
							5.600	High
Fourth	R8	Unit 42	Residential	LKD	W15	290°N	1.400	
							1.400	Failed
Fourth	R9	Unit 41	Residential	LD	W16	290°N	1.600	
					W17	290°N	1.400	
							1.600	Minimum
Fourth	R10	Unit 41	Residential	Kitchen	W18	290°N	0.000	
							0.000	Failed
Fourth	R11	Unit 40	Residential	Kitchen	W19	290°N	1.000	
							1.000	Failed
Fourth	R12	Unit 40	Residential	LD	W20	290°N	1.000	
					W21	290°N	1.000	
							1.000	Failed
Fourth	R13	Unit 48	Residential	LKD	W22	290°N	0.000	
							1.000	Failed
Fourth	R14	Unit 47	Residential	Bedroom	W23	20°N	0.000	
					W24	290°N	1.100	
							1.100	Failed
Fourth	R15	Unit 47	Residential	LKD	W25	290°N	1.100	
					W26	290°N	1.100	
					W27	200°	4.200	
					W28	200°	6.400	
							6.500	High
Fourth	R16	Unit 47	Residential	Bedroom	W29	200°	6.400	
							6.400	High
Fourth	R17	Unit 46	Residential	LKD	W30	200°	6.400	
					W31	200°	6.400	
							6.400	High
Fourth	R18	Unit 46	Residential	Bedroom	W32	200°	6.400	
							6.400	High
Fourth	R19	Unit 45	Residential	Bedroom	W33	200°	6.400	
					W34	200°	6.400	
							6.400	High
Fourth	R20	Unit 45	Residential	LKD	W35	200°	6.400	
					W36	200°	4.200	
							6.400	High
Fourth	R21	Unit 48	Residential	Bedroom	W37	110°	3.400	
							3.400	Medium
Fourth	R22	Unit 40	Residential	Bedroom	W38	110°	3.600	

							3.600	Medium
Fourth	R23	Unit 40	Residential	Bedroom	W39	110°	3.600	
							3.600	Medium
Fourth	R24	Unit 41	Residential	Bedroom	W40	110°	4.000	
							4.000	Medium
Fourth	R25	Unit 41	Residential	Bedroom	W41	110°	4.000	
							4.000	Medium
Fourth	R26	Unit 42	Residential	Bedroom	W42	110°	3.900	
							3.900	Medium

Property	Number of Rooms Tested	Rating				No. of Rooms Satisfying Criteria
		High	Medium	Minimum	Failed	
Proposed	126	32	23	8	63	63
Total	**126**	**32**	**23**	**8**	**63**	**63**

Property	Unit	Number of Rooms Tested	Rating				No. of Rooms Satisfying Criteria
			High	Medium	Minimum	Failed	
Proposed	Unit 05	4	0	0	1	3	1
Proposed	Unit 04	3	0	1	0	2	1
Proposed	Unit 03	1	0	0	0	1	0
Proposed	Unit 02	1	0	0	0	1	0
Proposed	Unit 01	1	0	0	0	1	0
Proposed	Unit 09	3	0	0	0	3	0
Proposed	Unit 08	2	0	0	0	2	0
Proposed	Unit 07	3	2	0	0	1	2
Proposed	Unit 06	4	4	0	0	0	4
Proposed	Unit 15	2	0	0	0	2	0
Proposed	Unit 14	2	0	0	0	2	0
Proposed	Unit 13	3	0	1	0	2	1
Proposed	Unit 12	2	0	0	0	2	0
Proposed	Unit 11	2	0	0	0	2	0
Proposed	Unit 10	2	0	0	0	2	0
Proposed	Unit 19	2	0	0	0	2	0
Proposed	Unit 18	3	2	0	0	1	2
Proposed	Unit 17	2	2	0	0	0	2
Proposed	Unit 16	2	2	0	0	0	2
Proposed	Unit 25	3	0	0	0	3	0
Proposed	Unit 24	1	0	0	0	1	0
Proposed	Unit 23	3	0	1	0	2	1
Proposed	Unit 22	3	0	0	1	2	1
Proposed	Unit 21	4	0	3	1	0	4
Proposed	Unit 20	4	0	3	1	0	4
Proposed	Unit 29	3	0	0	1	2	1
Proposed	Unit 28	3	2	0	0	1	2
Proposed	Unit 27	2	2	0	0	0	2
Proposed	Unit 26	2	2	0	0	0	2
Proposed	Unit 35	3	0	0	0	3	0
Proposed	Unit 34	1	0	0	0	1	0
Proposed	Unit 33	3	1	0	0	2	1
Proposed	Unit 32	3	0	1	0	2	1
Proposed	Unit 31	4	0	3	1	0	4
Proposed	Unit 30	4	0	3	1	0	4
Proposed	Unit 39	3	0	1	0	2	1
Proposed	Unit 38	3	2	0	0	1	2
Proposed	Unit 37	2	2	0	0	0	2
Proposed	Unit 36	2	2	0	0	0	2
Proposed	Unit 44	4	0	0	0	4	0
Proposed	Unit 43	3	1	0	0	2	1
Proposed	Unit 42	2	0	1	0	1	1
Proposed	Unit 41	4	0	2	1	1	3
Proposed	Unit 40	4	0	2	0	2	2
Proposed	Unit 48	2	0	1	0	1	1
Proposed	Unit 47	3	2	0	0	1	2

Proposed	Unit 46	2	2	0	0	0	2
Proposed	Unit 45	2	2	0	0	0	2
Total		**126**	**32**	**23**	**8**	**63**	**63**